

Air System Sizing Summary for Unit #2

Project Name: Coffey County Housing Authority - Triplex
 Prepared by: Schmidt Engineering Consultants, Inc

02/21/2016
 01:26PM

Air System Information

Air System Name:..... **Unit #2**
 Air System Type:..... **Single Zone CAV**
 Number of zones:..... **1**
 Floor Area:..... **1094.5** sqft
 Location:..... **Topeka, Kansas**

Sizing Calculation Information

Calculation Months:..... **Jan to Dec**
 Calculation method:..... **Transfer Function Method**

Central Cooling Coil Sizing Data

Total coil load:.....	0.8 Tons	Load occurs at:.....	Jul 1600
Total coil load:.....	10.0 MBH	OA DB / WB:.....	95.4/74.8 F
Sensible coil load:.....	8.2 MBH	Entering DB / WB:.....	79.3/66.3 F
Coil airflow:.....	383 CFM	Leaving DB / WB:.....	58.9/57.7 F
Sensible heat ratio:.....	0.816	Coil ADP:.....	56.6 F
Area per unit load:.....	1308.7 sqft/Ton	Bypass Factor:.....	0.100
Load per unit area:.....	9.2 BTU/(hr-sqft)	Resulting RH:.....	54 %
		Design supply temp:.....	58.0 F

Central Heating Coil Sizing Data

Max coil load:.....	12.2 MBH	Load occurs at:.....	Des Htg
Coil airflow:.....	383 CFM	Ent DB / Lvg DB:.....	55.6/86.1 F
Load per unit area:.....	11.2 BTU/(hr-sqft)		

Supply Fan Sizing Data

Actual max airflow:.....	383 CFM	Fan motor BHP:.....	0.00 BHP
Standard airflow:.....	371 CFM	Fan motor kW:.....	0.00 kW
Actual max airflow per unit area:.....	0.35 CFM/sqft	Fan static:.....	0.00 in wg

Outdoor Ventilation Air Data

Design airflow:.....	75 CFM	Airflow per person:.....	18.75 CFM/person
Airflow per unit floor area:.....	0.07 CFM/sqft		

Space Sizing Data

Space Name	Maximum Cooling Sensible Load MBH	Design Airflow CFM	Time of Peak Load	Maximum Heating Load MBH	Space Floor Area sqft	Space CFM/sqft
Bath(2)	0.2	9	Jul 1500	0.1	85.5	0.11
Bedroom #1(2)	1.2	65	Jul 1300	1.4	183.0	0.36
Bedroom #2(2)	1.5	85	Jul 1700	1.7	180.6	0.47
Corridor(2)	0.1	4	Jul 1500	0.1	39.1	0.11
Dining Room(2)	0.3	17	Jul 1400	0.3	165.5	0.11
Kitchen(2)	1.4	77	Jul 1400	1.1	142.7	0.54
Living Room(2)	1.8	102	Jul 1700	1.8	231.4	0.44
Utility(2)	0.6	36	Jul 1300	0.4	66.7	0.53
Zone	6.8	383	Jul 1600	6.9	1094.5	0.35

Note: Table contains data for all spaces controlled by a single thermostat:

Space sizing basis:..... **Peak space load**
 Zone sizing basis:..... **Peak zone load**

System Design Load Summary for Unit #2

Project Name: Coffey County Housing Authority - Triplex
 Prepared by: Schmidt Engineering Consultants, Inc

02/21/2016
 01:26PM

Zone Loads based on TFM	DESIGN COOLING			DESIGN HEATING		
	Jul 1600			Design Heating Day		
	OA DB / WB 95.4 F / 74.8 F			OA DB / WB -2 F / -3.4 F		
	Details	Sensible BTU/hr	Latent BTU/hr	Details	Sensible BTU/hr	Latent BTU/hr
Window and Skylight Solar Loads	45 sqft	1381	-	45 sqft	-	-
Wall Transmission	492 sqft	857	-	492 sqft	1522	-
Roof Transmission	1095 sqft	1961	-	1095 sqft	1891	-
Window Transmission	45 sqft	232	-	45 sqft	972	-
Skylight Transmission	0 sqft	0	-	0 sqft	0	-
Door Loads	40 sqft	131	-	40 sqft	550	-
Floor Transmission	1095 sqft	0	-	1095 sqft	1927	-
Partitions/Ceilings	0 sqft	0	-	0 sqft	0	-
Overhead Lighting	0 W	0	-	0 W	0	-
Electric Equipment	0 W	0	-	0 W	0	-
People	4	920	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	1325	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>>Total Zone Loads	-	6808	480	-	6863	0
Thermostat and Pulldown Adjustment	-	-189	0	-	-266	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Ventilation Load	75 CFM	1566	1371	75 CFM	5622	0
Supply Fan Load	383 CFM	0	-	383 CFM	0	-
>> Total System Loads	-	8185	1851	-	12219	0
Central Cooling Coil	-	8185	1851	-	0	0
Central Heating Coil	-	0	-	-	12219	-
>> Total Coil Loads	-	8185	1851	-	12219	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Zone Design Load Summary for Unit #2

Project Name: Coffey County Housing Authority - Triplex
 Prepared by: Schmidt Engineering Consultants, Inc

02/21/2016
 01:26PM

Bath(2)	DESIGN COOLING			DESIGN HEATING		
	Jul 1600			Design Heating Day		
	OA DB / WB 95.4 F / 74.8 F			OA DB / WB -2 F / -3.4 F		
	Thermostat Setpoint 75.0 F			Thermostat Setpoint 70.0 F		
Zone Loads based on TFM	Details	Sensible BTU/hr	Latent BTU/hr	Details	Sensible BTU/hr	Latent BTU/hr
Window and Skylight Solar Loads	45 sqft	1381	-	45 sqft	-	-
Wall Transmission	492 sqft	857	-	492 sqft	1522	-
Roof Transmission	1095 sqft	1961	-	1095 sqft	1891	-
Window Transmission	45 sqft	232	-	45 sqft	972	-
Skylight Transmission	0 sqft	0	-	0 sqft	0	-
Door Loads	40 sqft	131	-	40 sqft	550	-
Floor Transmission	1095 sqft	0	-	1095 sqft	1927	-
Partitions/Ceilings	0 sqft	0	-	0 sqft	0	-
Overhead Lighting	0 W	0	-	0 W	0	-
Electric Equipment	0 W	0	-	0 W	0	-
People	4	920	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	1325	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	6808	480	-	6863	0